



# ADMINISTRATIVE OFFICE OF THE COURTS

GOVERNMENT RELATIONS  
INFORMATION TECHNOLOGY  
INTERNAL AFFAIRS  
JUDICIAL COLLEGE OF MARYLAND  
**OPERATIONS**  
PROGRAMS

## Addendum No. 1 Judicial Center Parking Lot Asphalt Paving Repairs K17-0033-25 October 6, 2016

This Addendum is being issued to amend and clarify certain information contained in the above named small procurement RFP. All information contained herein is binding on all Offerors who respond to this small procurement RFP. Specific parts of the RFP have been amended. The following changes/additions are listed below; new language has been **underlined** and language deleted has been marked with a **~~strikeout~~** (ex. language deleted).

### 2.3 Contractor Requirements:

#### 2.3.1 General

##### A. Warranty

1. The contractor shall warrant for a period of two (2) years from the final acceptance date that the work and materials will, under normal use and service, be free from defects and faulty workmanship.

#### 2.3.2 Materials

- A. Asphalt for the new surface course shall be Hot Mix Asphalt Superpave 9.5mm, PG 64-22, Level 2, or approved equal.

#### 2.3.3 Execution

- A. All work shall be performed as called for in these written specifications.
- B. All work shall coordinated with the AOC Project Manager during the work initiation meeting.
- C. **All work shall be accomplished overnight after 6:00 P.M and before 6:00 A.M. ~~or on a single Saturday.~~**
- D. The completed work will be subject to inspection and approval of the AOC Project Manager.

**2.3.4 Parking Lot Measurements:**

**Lot J- Full Depth Patching- 305 square yards**

**Lot J- Mill and Overlay- 2,305 square yards**

**Lot J- Option A- 185 square yards**

**Lot K- Full Depth Patching- 155 square yards**

Date Issued: October 6, 2016

Issued by: April Molley, Procurement Officer

**ATTACHMENT E – PRICE PROPOSAL FORM**

**Judicial Center Parking Lot Asphalt Paving Repairs**

**PRICE PROPOSAL FOR RFP # K17-0033-25**

Total Price of Project  (without 2.2.1 #8):	\$ _____
Pricing for 2.2.1#8:  Seal coat the paved area between the newly paved parking lot and Sachs Drive.	\$ _____
Pricing for 2.2.2  Option 1: A. Mill and repave the paved area between the newly paved parking lot and Sachs Drive to remove the existing surface course. Overlay the milled area with 2"-3" of new surface course asphalt. Coordinate with the Judiciary's security contractor for the installation of new ground loops detectors for the gate system.	\$ _____

<b>Unit Prices</b>	
<b><u>Subgrade Preparation Cost Per Square Yard (SY) with 2" compacted depth</u></b>	\$ _____
<b><u>Aggregate Base Course (ABC) Cost Per Square Yard (SY) with 2-1/2" compacted depth.</u></b>	\$ _____
<b><u>Contingency MOT stones needed _____ tons at:</u></b>	\$ _____ per ton
<b><u>MOT stones storage truck cost.</u></b>	\$ _____

\_\_\_\_\_  
Authorized Individual Name/Date

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Title

\_\_\_\_\_  
Company Federal Tax ID #